

Date: November 8, 2017

Mattern & Craig
Consulting Engineers
701 First Street, S.W.
Roanoke, Virginia 24016

Project: FY18 Bridge Rehabilitation Project, City of Staunton, Virginia

Commission No: 3659

Addendum Date: November 8, 2017

Addendum No: 3

Includes Full Size Plan Sheets: Yes ✓ No

The following shall modify the contract documents and the work shall be accomplished in accordance with such modifications. It is requested that this Addendum be stapled to the back of the front cover of the specifications.

- ITEM #1:** The Record Drawings for Structure 1809 indicate Beam 14 is a W14 x 73. The As-Built Bridge Plans for Structure 1027 indicate the beams are W36 x 150 with partial length 3/4" x 9-1/2" bottom cover plates and the end diaphragms are C15 x 33.9.
- ITEM #2:** **REPLACE** the "Bid" document with the attached "Bid" document. Bid Item "Embedded Galvanic Anode" was added to all four structures.
- ITEM #3:** In Advertisement for Bids and Information for Bidders Section 1, the Bid receipt date is **CHANGED** to 2:00 p.m., November 20, 2017 as noted in Addendum #2.

ADDENDUM #3

BID

FY18 BRIDGE REHABILITATION PROJECT

TO: City of Staunton
City Hall
P.O. Box 58
Staunton, Virginia 24402

Gentlemen:

The undersigned, as Bidder, does hereby declare that the only person, persons, company or parties interested in this Bid are named herein; that this Bid is made and that the Contract will be executed without collusion with any other person or persons presenting any Bid for the same work, labor and materials; that this Bid is in all respects fair and just and that no person prohibited therefrom by law is directly or indirectly interested in this Bid, nor in the labor and materials to which it relates, nor in any portion of the profits thereof.

The undersigned does further declare that he has personally examined the site of the proposed work and made such investigation as is necessary to determine the general and local conditions and the character of the work to be encountered; that he was carefully examined each and every item of the annexed Contract Documents and the Plans and Specifications pertaining hereto, and that he fully understands the same, and will make no claim, other than as stated therein, because of any misunderstanding or misconception concerning the nature, charter or amount of work to be done.

The undersigned does hereby offer and agree to execute and perform the Contract attached hereto, and of which this Bid forms a part; and to furnish all of the labor, materials, tools, equipment, transportation and superintendence for the construction; in strict conformity with the drawings and specifications. The undersigned further proposes to perform the work at the prices set opposite each item, it being understood that the quantities given are estimates only and payment will be made on the basis of actual quantities as developed during the construction.

BID SCHEDULE**Structure 1027
US Route 250 (WBL Richmond Rd) over CSX Railway**

BID NO.	ITEM	UNITS	EST QTY	UNIT PRICE	TOTAL PRICE
1a	Preformed Elastomeric Joint Sealer – 2 1/2" *	LF	189		
1b	Preformed Elastomeric Joint Sealer – 3" *	LF	63		
2	Epoxy Mortar Joint Repair	LF	20		
3	Repair Epoxy Overlay	SY	4		
4	Type B Patching (HES)	SY	1		
5	Concrete Superstructure Surface Repairs	SY	4		
6	Concrete Substructure Surface Repairs	SY	15		
7	Zone Coating of Beam Ends, Diaphragms, and Bearings	LS	1		
8	Replace Anchor Bolt	EA	1		
9	Waterproofing – Parapets *	LF	390		
10	Waterproofing – (Epoxy Resin EP-3B / EP-3T) – Pier Bearing Seats *	SY	46		
11	Railroad Coordination	LS	1		
12	Maintenance of Traffic	LS	1		
13	Mobilization	LS	1		
14	Embedded Galvanic Anode	EA	150		
	SUBTOTAL – STRUCTURE NO. 1027				

BID SCHEDULE**Structure 1802
US Route 11 (Commerce Rd) over State Route 254 (New Hope Rd) and Lewis Creek**

BID NO.	ITEM	UNITS	EST QTY	UNIT PRICE	TOTAL PRICE
1	(HMWM) Concrete Surface Treatment *	SY	1026		
1a	Type B Patching (HES)	SY	1		
2	Concrete Substructure Surface Repairs	SY	40		
3	Waterproofing – Parapets *	LF	324		
4	Waterproofing – Pier Wall	LS	1		
5	Waterproofing – Penetrant Sealer For Median and Curbs *	SY	90		
6	Maintenance of Traffic	LS	1		
7	Mobilization	LS	1		
8	Embedded Galvanic Anode	EA	300		
	SUBTOTAL – STRUCTURE NO. 1802				

BID SCHEDULE

**Structure 1809
US Routes 11, 250 and State Route 254
(Greenville Ave and Commerce Rd) over Lewis Creek**

BID NO.	ITEM	UNITS	EST QTY	UNIT PRICE	TOTAL PRICE
1	Repair Stone Masonry Abutments	SF	120		
2	(HMWM) Concrete Surface Treatment *	SY	217		
3	Crack Repair (Type A) in Longitudinal Construction Joint *	LF	33		
4	Zone Coating of Beam 14	LS	1		
5	Concrete Superstructure Surface Repairs	SY	5		
6	Concrete Substructure Surface Repairs	SY	4		
7	Jacking and Blocking Beams	EA	3		
8	Maintenance of Traffic	LS	1		
9	Mobilization	LS	1		
10	Embedded Galvanic Anode	EA	70		
	SUBTOTAL – STRUCTURE NO. 1809				

BID SCHEDULE

Structure 8001
State Route 261 (Statler Blvd) over CSX Railway and Private Road

BID NO.	ITEM	UNITS	EST QTY	UNIT PRICE	TOTAL PRICE
1	Concrete Substructure Surface Repairs	SY	10		
2	Concrete Superstructure Surface Repairs	SY	2		
3	Type B Patching (HES)	SY	2		
4	Replace Concrete Slope Protection	SY	6		
5	Waterproofing – Penetrant Sealer For Top of Deck, Median, Sidewalks, Curbs, and Approach Slabs *	SY	1964		
6a	Preformed Elastomeric Joint Sealer – 1 3/4" *	LF	172		
6b	Preformed Elastomeric Joint Sealer – 2" *	LF	258		
7	Epoxy Mortar Joint Repair	LF	100		
8	Replace Joint Sealant *	LF	116		
9	Waterproofing – (Epoxy Resin EP-3B / EP-3T) – Pier Bearing Seats *	SY	92		
10	Waterproofing – Parapets *	LF	388		
11	Railroad Coordination	LS	1		
12	Maintenance of Traffic	LS	1		
13	Mobilization	LS	1		
14	Embedded Galvanic Anode	EA	50		
	SUBTOTAL – STRUCTURE NO. 8001				

* ITEM SHALL BE MEASURED AND PAID FOR ON THE BASIS OF PLAN QUANTITIES. NO ADDITIONAL MEASUREMENT SHALL BE MADE.

TOTAL BASE BID (SUM OF SUBTOTALS FOR STRUCTURES 1027, 1802, 1809 and 8001):

_____ (\$ _____)
WORDS **FIGURES**

AMOUNTS ARE TO BE SHOWN IN BOTH WORDS AND FIGURES. IN CASE OF DISCREPANCY, THE AMOUNT SHOWN IN WORDS WILL GOVERN.

The undersigned agrees to complete the work enumerated herein **in accordance with Paragraph 9 of Information for Bidders**. It is expressly understood and agreed that the time of beginning, rate of progress, and the date of completion are essential conditions, and that in the event of failure to complete the work within the above specified time, the Contractor will be liable for the payment of liquidated damages as provided in **Paragraph 9 of Information for Bidders**. Extensions may be granted, upon written request, for inclement weather and for any other cause not the fault of the Contractor. The City reserves the right to shut the project down for extended periods due to inclement weather. Deadline extensions will be made to equally compensate for periods of shut down.

The undersigned likewise agrees that he will execute and deliver the Contract hereto attached within ten (10) days, Sundays and holidays excepted, after notification of the acceptance of this Bid and award of the Contract; and will furnish a performance and a payment bond for the total amount of the accepted Bid on the forms provided in the Contract Documents, satisfactory to the Owner as surety for the faithful performance and completion of the Contract and the payment of all subcontractors, material dealers and labor.

The undersigned certifies that he understands that it is the intent of the drawings, and the Contract Documents, that the work be completed in every respect and that no additional compensation will be allowed for minor tasks necessary to completely perform the work.

The undersigned acknowledges Addenda:

Addenda No. _____	Addenda _____
Addenda No. _____	Addenda _____

The undersigned has checked carefully all the above figures and understands that the Owner will not be responsible for any errors or omissions in making up this Bid.

_____ Contractor	By: _____ Printed Name: _____ Title: _____
_____ Registered Virginia Contract Number	Address: _____ _____
_____ SCC Number	_____
_____ Contractor's IRS Number	Telephone: _____

Dates this ____ day of _____, 20____