WESTERN STATE HOSPITAL
HAZARDOUS MATERIALS SURVEY

LAB ANALYSIS
BUILDING #107

*208 Walnut Hills Road • **Staunton**, VA 24401 • Tel: (540) 337-3740 • Fax: (540) 337-9075*
Email: mhart @ei1.com • Online: www.ei1.com

SanAir Technologies Laboratory

Analysis Report

prepared for

EI Group, Inc Roanoke Office

Report Date: 9/12/2013
Project Name: Wstn State Hosp
Project #: 196
SanAir ID#: 13021271

NVLAP LAB CODE 200870-0

AIHA LAP, LLC ACCREDITED LABORATORY ENVIRONMENTAL MICROBIOLOGY

Virginia SBE Certification # 652931

Texas Licensed Mold Analysis Laboratory License # LAB0166

SanAir Technologies Laboratory

804.897.1177 www.sanair.com

208 Walnut Hills Road • **Staunton**, VA 24401 • Tel: (540) 337-3740 • Fax: (540) 337-9075
Email: mhart @ei1.com • Online: www.ei1.com

SanAir Technologies Laboratory, Inc.
1551 Oakbridge Drive, Suite B, Powhatan, VA 23139
804.897.1177 Toll Free: 888.895.1177 Fax: 804.897.0070
Web: http://www.sanair.com E-mail: iaq@sanair.com

EI Group, Inc Roanoke Office
15 Salem Ave SE
Suite 301
Roanoke, VA 24011

September 12, 2013

SanAir ID # 13021271
Project Name: Wstn State Hosp
Project Number: 196

Dear Melissa Hart,

We at SanAir would like to thank you for the work you recently submitted. The 30 sample(s) were received on Wednesday, September 11, 2013 via FedEx. The final report(s) is enclosed for the following sample(s): 107-1, 107-2, 107-3, 107-4, 107-5, 107-6, 107-7, 107-8, 107-9, 107-10, 107-11, 107-12, 107-13, 107-14, 107-15, 107-16, 107-17, 107-18, 107-19, 107-20, 107-21, 107-22, 107-23, 107-24, 107-25, 107-26, 107-27, 107-28, 107-29, 107-30.

These results only pertain to this job and should not be used in the interpretation of any other job. This report is only complete in its entirety. Refer to the listing below of the pages included in a complete final report.

Sincerely,

Sandra Sobrino

Sandra Sobrino
Asbestos & Materials Laboratory Manager
SanAir Technologies Laboratory

Final Report Includes:
- Cover Letter
- Analysis Pages
- Disclaimers and Additional Information

sample conditions:
30 sample(s) in Good condition

SanAir Technologies Laboratory, Inc.

1551 Oakbridge Drive, Suite B, Powhatan, VA 23139
804.897.1177 Toll Free: 888.895.1177 Fax: 804.897.0070
Web: http://www.sanair.com E-mail: iaq@sanair.com

SanAir ID Number
13021271
FINAL REPORT

Name: EI Group, Inc Roanoke Office
Address: 15 Salem Ave SE
Suite 301
Roanoke, VA 24011

Project Number: 196
P.O. Number: Bldg 107
Project Name: Wstn State Hosp

Collected Date: 9/10/2013
Received Date: 9/11/2013 10:10:00 AM
Report Date: 9/12/2013 12:14:23 PM
Analyst: Childress, Susan

Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-1 / 13021271-001 Ceiling Tile	White Fibrous Homogeneous	55% Cellulose 35% Glass	10% Other	None Detected
107-1 / 13021271-001 Mastic	Brown Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-2 / 13021271-002 Ceiling Tile	White Fibrous Homogeneous	55% Cellulose 35% Glass	10% Other	None Detected
107-2 / 13021271-002 Mastic	Brown Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-3 / 13021271-003 Cove Base	Red Non-Fibrous Homogeneous		100% Other	None Detected
107-3 / 13021271-003 Mastic	Black Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-4 / 13021271-004 Cove Base	Red Non-Fibrous Homogeneous		100% Other	None Detected
107-4 / 13021271-004 Mastic	Black Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-5 / 13021271-005 Cove Base	Black Non-Fibrous Homogeneous		100% Other	None Detected
107-5 / 13021271-005 Mastic	Yellow Non-Fibrous Homogeneous		100% Other	None Detected

Certification

Signature: Susan P. Childress
Date: 9/12/2013

Reviewed: Sandra Sobrino
Date: 9/12/2013

SanAir Technologies Laboratory, Inc.
1551 Oakbridge Drive, Suite B, Powhatan, VA 23139
804.897.1177 Toll Free: 888.895.1177 Fax: 804.897.0070
Web: http://www.sanair.com E-mail: iaq@sanair.com

SanAir ID Number
13021271
FINAL REPORT

Name: EI Group, Inc Roanoke Office
Address: 15 Salem Ave SE
Suite 301
Roanoke, VA 24011

Project Number: 196
P.O. Number: Bldg 107
Project Name: Wstn State Hosp

Collected Date: 9/10/2013
Received Date: 9/11/2013 10:10:00 AM
Report Date: 9/12/2013 12:14:23 PM
Analyst: Childress, Susan

Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-6 / 13021271-006 Cove Base	Black Non-Fibrous Homogeneous		100% Other	None Detected
107-6 / 13021271-006 Mastic	Yellow Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-7 / 13021271-007 Floor Tile	Beige Non-Fibrous Homogeneous		100% Other	None Detected
107-7 / 13021271-007 Mastic	Yellow Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-8 / 13021271-008 Floor Tile	Beige Non-Fibrous Homogeneous		100% Other	None Detected
107-8 / 13021271-008 Mastic	Yellow Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-9 / 13021271-009	White Fibrous Homogeneous	60% Cellulose 30% Glass	10% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-10 / 13021271-010	White Fibrous Homogeneous	60% Cellulose 30% Glass	10% Other	None Detected

Certification

Signature: Susan P. Childress
Date: 9/12/2013

Reviewed: Sandra Sobrino
Date: 9/12/2013

SanAir Technologies Laboratory, Inc.
1551 Oakbridge Drive, Suite B, Powhatan, VA 23139
804.897.1177 Toll Free: 888.895.1177 Fax: 804.897.0070
Web: http://www.sanair.com E-mail: iaq@sanair.com

SanAir ID Number
13021271
FINAL REPORT

Name: EI Group, Inc Roanoke Office
Address: 15 Salem Ave SE
Suite 301
Roanoke, VA 24011

Project Number: 196
P.O. Number: Bldg 107
Project Name: Wstn State Hosp

Collected Date: 9/10/2013
Received Date: 9/11/2013 10:10:00 AM
Report Date: 9/12/2013 12:14:23 PM
Analyst: Childress, Susan

Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-11 / 13021271-011 Plaster	Brown Non-Fibrous Homogeneous		100% Other	None Detected
107-11 / 13021271-011 Skim Coat	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-12 / 13021271-012 Plaster	Brown Non-Fibrous Homogeneous		100% Other	None Detected
107-12 / 13021271-012 Skim Coat	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-13 / 13021271-013 Soft Material	Red Non-Fibrous Homogeneous	2% Glass	98% Other	None Detected
107-13 / 13021271-013 Texture	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-14 / 13021271-014 Soft Material	Red Non-Fibrous Homogeneous	2% Glass	98% Other	None Detected
107-14 / 13021271-014 Texture	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-15 / 13021271-015 Ceiling Tile	White Fibrous Homogeneous	85% Glass	15% Other	None Detected
107-15 / 13021271-015 Mastic	Brown Non-Fibrous Homogeneous		100% Other	None Detected

Certification

Signature: Susan P. Childress
Date: 9/12/2013

Reviewed: Sandra Sobrino
Date: 9/12/2013

SanAir Technologies Laboratory, Inc.
1551 Oakbridge Drive, Suite B, Powhatan, VA 23139
804.897.1177 Toll Free: 888.895.1177 Fax: 804.897.0070
Web: http://www.sanair.com E-mail: iaq@sanair.com

SanAir ID Number
13021271
FINAL REPORT

Name: EI Group, Inc Roanoke Office
Address: 15 Salem Ave SE
Suite 301
Roanoke, VA 24011

Project Number: 196
P.O. Number: Bldg 107
Project Name: Wstn State Hosp

Collected Date: 9/10/2013
Received Date: 9/11/2013 10:10:00 AM
Report Date: 9/12/2013 12:14:23 PM
Analyst: Childress, Susan

Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-16 / 13021271-016 Ceiling Tile	White Fibrous Homogeneous	85% Glass	15% Other	None Detected
107-16 / 13021271-016 Mastic	Brown Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-17 / 13021271-017 Plaster	Brown Non-Fibrous Homogeneous		100% Other	None Detected
107-17 / 13021271-017 Skim Coat	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-18 / 13021271-018 Plaster	Brown Non-Fibrous Homogeneous		100% Other	None Detected
107-18 / 13021271-018 Skim Coat	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-19 / 13021271-019 Cove Base	Grey Non-Fibrous Homogeneous		100% Other	None Detected
107-19 / 13021271-019 Mastic	Yellow Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-20 / 13021271-020 Cove Base	Grey Non-Fibrous Homogeneous		100% Other	None Detected
107-20 / 13021271-020 Mastic	Yellow Non-Fibrous Homogeneous		100% Other	None Detected

Certification

Signature: Susan P. Childress
Date: 9/12/2013

Reviewed: Sandra Sobrino
Date: 9/12/2013

SanAir Technologies Laboratory, Inc.
1551 Oakbridge Drive, Suite B, Powhatan, VA 23139
804.897.1177 Toll Free: 888.895.1177 Fax: 804.897.0070
Web: http://www.sanair.com E-mail: iaq@sanair.com

SanAir ID Number
13021271
FINAL REPORT

Name: EI Group, Inc Roanoke Office
Address: 15 Salem Ave SE
Suite 301
Roanoke, VA 24011

Project Number: 196
P.O. Number: Bldg 107
Project Name: Wstn State Hosp

Collected Date: 9/10/2013
Received Date: 9/11/2013 10:10:00 AM
Report Date: 9/12/2013 12:14:23 PM
Analyst: Childress, Susan

Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-21 / 13021271-021 Drywall	Off-White Non-Fibrous Homogeneous	2% Cellulose	98% Other	None Detected
107-21 / 13021271-021 Joint Compound	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-22 / 13021271-022 Drywall	Off-White Non-Fibrous Homogeneous	2% Cellulose	98% Other	None Detected
107-22 / 13021271-022 Joint Compound	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-23 / 13021271-023	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-24 / 13021271-024	White Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-25 / 13021271-025	Grey Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-26 / 13021271-026	Grey Non-Fibrous Homogeneous		100% Other	None Detected

Certification

Signature: Susan P. Childress
Date: 9/12/2013

Reviewed: Sandra Sobrino
Date: 9/12/2013

SanAir Technologies Laboratory, Inc.
1551 Oakbridge Drive, Suite B, Powhatan, VA 23139
804.897.1177 Toll Free: 888.895.1177 Fax: 804.897.0070
Web: http://www.sanair.com E-mail: iaq@sanair.com

SanAir ID Number
13021271
FINAL REPORT

Name: EI Group, Inc Roanoke Office
Address: 15 Salem Ave SE
Suite 301
Roanoke, VA 24011

Project Number: 196
P.O. Number: Bldg 107
Project Name: Wstn State Hosp

Collected Date: 9/10/2013
Received Date: 9/11/2013 10:10:00 AM
Report Date: 9/12/2013 12:14:23 PM
Analyst: Childress, Susan

Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-27 / 13021271-027	Grey Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-28 / 13021271-028	Grey Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-29 / 13021271-029	Grey Non-Fibrous Homogeneous		100% Other	None Detected

SanAir ID / Description	Stereoscopic Appearance	Components % Fibrous	Components % Non-Fibrous	Asbestos Fibers
107-30 / 13021271-030	Grey Non-Fibrous Homogeneous		100% Other	None Detected

Certification

Signature: Susan P. Childress
Date: 9/12/2013

Reviewed: Sandra Sobrino
Date: 9/12/2013

Disclaimer

The final report cannot be reproduced, except in full, without written authorization from SanAir. Fibers smaller than 5 microns cannot be seen with this method due to scope limitations. The accuracy of the results is dependent upon the client's sampling procedure and information provided to the laboratory by the client. SanAir assumes no responsibility for the sampling procedure and will provide evaluation reports based solely on the sample and information provided by the client. This report may not be used by the client to claim product endorsement by NVLAP or any other agency of the U.S. government.

For NY state samples, method EPA 600/M4-82-020 is performed.

Polarized- light microscopy is not consistently reliable in detecting asbestos in floor covering and similar non-friable organically bound materials. Quantitative transmission electron microscopy is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos containing.

NY ELAP lab ID 11983

SanAir Technologies Laboratory, Inc.

1551 Oakbridge Drive, Suite B - Powhatan, VA 23139
804-897-1177 / 888-895-1177 / Fax 804-897-0070
www.sanair.com

Asbestos Chain of Custody

SanAir ID Number 1302127

Company: E.T	Project #: 156	Collect by:
Address:	Project Name: WSTN STATE Hosp	Phone #:
City, St., Zip:	Date Collected: Bldg 107	Fax #:
State of Collection: Account#:	P.O. Number:	Email:

Bulk

ABB	PLM EPA 600/R-93/116	☑
	Positive Stop ☐	
ABEPA	PLM EPA 400 Point Count	☐
ABB1K	PLM EPA 1000 Point Count	☐
ABBEN	PLM EPA NOB	☐
ABBCH	TEM Chatfield	☐
ABBTM	TEM EPA NOB	☐

Water

ABHE	EPA 100.2	☐

Air

ABA	PCM NIOSH 7400	☐
ABA-2	OSHA w/ TWA*	☐
ABTEM	TEM AHERA	☐
ABATN	TEM NIOSH 7402	☐
ABT2	TEM Level II	☐

New York ELAP

PLM NY	PLM 600/M4/82/020	☐
ABEPA2	NY ELAP 198.1	☐
ABENY	NY ELAP 198.6 PLM NOB	☐
ABBNY	NY ELAP 198.4 TEM NOB	☐

Soil/Vermiculite

ABSE	PLM EPA 600/R-93/116 (Qual.)	☐
ABSP	PLM CARB 435 (LOD <1%)	☐
ABSP1	PLM CARB 435 (LOD 0.25%)	☐
ABSP2	PLM CARB 435 (LOD 0.1%)	☐

Dust

ABWA	TEM Wipe ASTM D-6480	☐
ABDMV	TEM Microvac ASTM D-5755	☐

Matrix	Other	
		☐

Turn Around Times				
	3 HR (4 HR TEM) ☐	6 HR (8HR TEM) ☐	12 HR ☐	24 HR ☑
	2 Days ☐	3 Days ☐	4 Days ☐	5 Days ☐

Special Instructions

Sample #	Sample Identification/Location	Volume or Area	Sample Type	Flow Rate*	Time* Start – Stop	
107-001						
002						
003						
004						
005						
006						
007						
008						
009						
010						
011						
012						

Relinquished by	Date	Time	Received by	Date	Time
[illegible]	9-10-13		[illegible]	SEP 11 2013	10:10 AM

Unless scheduled, the turn around time for all samples received after 3 pm EST Friday will begin at 8 am Monday morning. Weekend or Holiday work must be scheduled ahead of time and is charged for rush turn around time. Work with standard turn around time sent Priority Overnight and Billed To Recipient will be charged a $10 shipping fee.

*208 Walnut Hills Road • **Staunton**, VA 24401 • Tel: (540) 337-3740 • Fax: (540) 337-9075*
Email: mhart @ei1.com • Online: www.ei1.com

SanAir Technologies Laboratory, Inc.

1551 Oakbridge Drive, Suite B - Powhatan, VA 23139
804-897-1177 / 888-895-1177 / Fax 804-897-0070
www.sanair.com

Asbestos Chain of Custody

SanAir ID Number: 13021271

Company: EI	Project #: 196	Collect by:
Address:	Project Name: USTA -STATE Hosp	Phone #:
City, St., Zip:	Date Collected: Bldg 107	Fax #:
State of Collection: Account#:	P.O. Number:	Email:

Bulk

ABB	PLM EPA 600/R-93/116	☑
	Positive Stop ☐	
ABEPA	PLM EPA 400 Point Count	☐
ABB1K	PLM EPA 1000 Point Count	☐
ABBEN	PLM EPA NOB	☐
ABBCH	TEM Chatfield	☐
ABBTM	TEM EPA NOB	☐

Water

ABHE	EPA 100.2	☐

Air

ABA	PCM NIOSH 7400	☐
ABA-2	OSHA w/ TWA*	☐
ABTEM	TEM AHERA	☐
ABATN	TEM NIOSH 7402	☐
ABT2	TEM Level II	☐

New York ELAP

PLM NY	PLM 600/M4/82/020	☐
ABEPA2	NY ELAP 198.1	☐
ABENY	NY ELAP 198.6 PLM NOB	☐
ABBNY	NY ELAP 198.4 TEM NOB	☐

Soil/Vermiculite

ABSE	PLM EPA 600/R-93/116 (Qual.)	☐
ABSP	PLM CARB 435 (LOD <1%)	☐
ABSP1	PLM CARB 435 (LOD 0.25%)	☐
ABSP2	PLM CARB 435 (LOD 0.1%)	☐

Dust

ABWA	TEM Wipe ASTM D-6480	☐
ABDMV	TEM Microvac ASTM D-5755	☐

Matrix	Other	
		☐

Turn Around Times				
	3 HR (4 HR TEM) ☐	6 HR (8HR TEM) ☐	12 HR ☐	24 HR ☑
	2 Days ☐	3 Days ☐	4 Days ☐	5 Days ☐

Special Instructions:

Sample #	Sample Identification/Location	Volume or Area	Sample Type	Flow Rate*	Time* Start – Stop	
107-013						
014						
015						
016						
017						
018						
019						
020						
021						
022						
023						
024						

Relinquished by	Date	Time	Received by	Date	Time
[illegible]	9-10-13		[illegible]	SEP 11 2013	10:10 AM

Unless scheduled, the turn around time for all samples received after 3 pm EST Friday will begin at 8 am Monday morning. Weekend or Holiday work must be scheduled ahead of time and is charged for rush turn around time. Work with standard turn around time sent Priority Overnight and Billed To Recipient will be charged a $10 shipping fee.

Page ___of ____

SanAir Technologies Laboratory, Inc.
1551 Oakbridge Drive, Suite B - Powhatan, VA 23139
804-897-1177 / 888-895-1177 / Fax 804-897-0070
www.sanair.com

Asbestos Chain of Custody

SanAir ID Number: 1302127

Company: EI	Project #: 196	Collect by:
Address:	Project Name: 45th State Hosp	Phone #:
City, St., Zip:	Date Collected: Bldg 107	Fax #:
State of Collection: Account#:	P.O. Number:	Email:

Bulk

ABB	PLM EPA 600/R-93/116	☑
	Positive Stop ☐	
ABEPA	PLM EPA 400 Point Count	☐
ABB1K	PLM EPA 1000 Point Count	☐
ABBEN	PLM EPA NOB	☐
ABBCH	TEM Chatfield	☐
ABBTM	TEM EPA NOB	☐

Air

ABA	PCM NIOSH 7400	☐
ABA-2	OSHA w/ TWA*	☐
ABTEM	TEM AHERA	☐
ABATN	TEM NIOSH 7402	☐
ABT2	TEM Level II	☐

Soil/Vermiculite

ABSE	PLM EPA 600/R-93/116 (Qual.)	☐
ABSP	PLM CARB 435 (LOD <1%)	☐
ABSP1	PLM CARB 435 (LOD 0.25%)	☐
ABSP2	PLM CARB 435 (LOD 0.1%)	☐

Dust

ABWA	TEM Wipe ASTM D-6480	☐
ABDMV	TEM Microvac ASTM D-5755	☐

New York ELAP

PLM NY	PLM 600/M4/82/020	☐
ABEPA2	NY ELAP 198.1	☐
ABENY	NY ELAP 198.6 PLM NOB	☐
ABBNY	NY ELAP 198.4 TEM NOB	☐

Water

ABHE	EPA 100.2	☐

Matrix	Other	
		☐

Turn Around Times				
	3 HR (4 HR TEM) ☐	6 HR (8HR TEM) ☐	12 HR ☐	24 HR ☑
	2 Days ☐	3 Days ☐	4 Days ☐	5 Days ☐

Special Instructions

Sample #	Sample Identification/Location	Volume or Area	Sample Type	Flow Rate*	Time* Start – Stop	
107-025						
026						
027						
028						
029						
030						

Relinquished by	Date	Time	Received by	Date	Time
[signature]	9-10-13		[signature]	SEP 11 2013	10:10AM

Unless scheduled, the turn around time for all samples received after 3 pm EST Friday will begin at 8 am Monday morning. Weekend or Holiday work must be scheduled ahead of time and is charged for rush turn around time. Work with standard turn around time sent Priority Overnight and Billed To Recipient will be charged a $10 shipping fee.

Page ___of ____